

Magnum

12.4 or 15.6 metres

For arable and grassland



Standard equipment:

- Self-cleaning Prismenwalze® Ø 45/50 cm **cast iron**
- Pendular elements with **3D ground contouring**
- Drawbar with hitch cat. 3
- Transport wheels 15,0/55-17 10 PR (**1240**) or 19,0/45-17 14 P (**1560**)
- Hydraulic folding
- 2-circuit air brake system
- Road lighting kit (LED)
- **Expert report required to obtain the general operating licence for driving on public road**

Standard machine

Type	Working width	Transport width	Num. of sections	Support load	Axle load	Weight	Item no.	Price excl. VAT
Magnum 1240	12.30 m	3.00 m	8	2,990 kg	3,410 kg*	6,400 kg	5102 1000-3	
Magnum 1560	15.60 m	3.00 m	10	3,730 kg	4,630 kg*	8,360 kg	9701 1010	

Options

Description	Note	Weight	Item no.	Price excl. VAT
Wheels 19,0/45-17 14 PR	surcharge on wheels 15,0/55-17 10 PR for Magnum 1240	120 kg	5102 1180	
NonStop-harrow for Magnum 1240	3-rows, 12 mm tines, space between tines 62.5 mm	2,300 kg	5001 4000-1	
	harrow hydraulically height-adjustable	200 kg	5001 2630	
NonStop-harrow for Magnum 1240	2-rows, with levelling bar, space between tines 75 mm	2,300 kg	5001 4100-1	
	harrow hydraulically height-adjustable	200 kg	5001 2630	
NonStop-harrow for Magnum 1240	2-rows, with Ripperboard, space between tines 37.5 mm	2,450 kg	5001 4200-1	
	Ripperboard hydraulically tilt-adjustable	200 kg	5001 4220	
NonStop-attachment reinforced gauge wheels 195/55	surcharge on wheels 18 x 8.5	50 kg	5001 2760	
Hydraulic pressure compensation 1240 1560	incl. throttle screw, manometre, gas accumulator for a constant pressure distribution to the cantilvers		5102 1500	
Loose tines on drawbar	4 tines mounted at drawbar quick-change system for points with swept point	300 kg	5101 0051-1	
Loose tines on NonStop	1 tine 4 pieces recommended for NonStop	8 kg	9700 9594	
Adapter loose tines	If NonStop collides with tractor tyres	63 kg	9701 3742	

Additional information

Additional information	Note
NonStop-harrow	standard with straight tines (Item no. see above). optional with cranked tines (Item no. without -1), same price.
Final assembly roller on-site: Final assemb. NonStop-harrow on-site:	approx. 3 hours approx. 2 hours
Hydraulic connections required:	2x da (Master - folding and transport wheels) 1x da (for hydraulic tilt adjustment Ripperboard) 1x da (for hydraulic height adjustment harrow)



Consider the traffic regulations! See page 5.

Front implements 1240



NonStop-harrow 3-rows
Item no. 5001 4000-1



NonStop-harrow 2-rows
with levelling bar
Item no. 5001 4100-1



NonStop-harrow 2-rows
with Ripperboard
Item no. 5001 4200-1
Option: hydraulic tilt adjustment for
Ripperboard